

Hatchery Building, Broonies Taing, Sandwick, Shetland ZE2 9HH Tel. No. [01950] 431513 Also at -

Fjakari, Ocraquoy, Cunningsburgh, Shetland ZE2 9HA Tel Frank:07795964599 David:07795682885 e-mail: enquiries@scd-limited.co.uk

www.scd-limited.co.uk

COMPONENT SPECIFICATION TIMBER FRAMED KIT HOUSE



FOUNDATIONS

Block Clad Concrete strip foundations 600x150mm with block-work

cavity wall [external walls] and 450x150mm with 150mm single skin block-work wall [internal support walls]

construction to under-building.

Timber Clad Concrete strip foundation 600x150mm [external walls]

and 450x150mm [internal support walls] with 150mm single skin block-work wall construction to under-building.

SOLUM Hard-core blinded infill, polythene Damp Proof

Membrane, 50mm concrete screed with ventilated air

space under joists

GROUND FLOOR

D.P.C. 150mm PVC

Wallplate 38x139mm CLS treated

Joists 45x195mm treated regularised whitewood

@ 400mm centres

Heating "biscuit" 9mm OSB in heating support decking,

47x50mm framing, 50mm heating screed

incorporating heating pipe-work.

Flooring 18mm thick Moisture Resistant T&G

Chipboard flooring, glued and screwed.

EXTERNAL WALL PANELS

Runners 6"x2" CLS treated

Studs 6"x2" CLS treated at 600mm centres

Sheathing 9mm OSB

Firestops 38x50mm whitewood o/saw treated Lintols [3] No. 38x184mm CLS treated

Headbinder 6"x2" CLS treated

Flitch Beam To Structural Engineer's specification.

EXTERNAL WALL CLADDING

Timber Clad 22x145mm whitewood treated scalloped

boarding on 38x50mm whitewood o/saw treated battens, fixed with marine grade

stainless steel nails.

Block Clad 100mm harled concrete block-work.



NON LOAD-BEARING INTERNAL PARTITIONS

Runners 38x89mm CLS treated

Studs 38x89mm CLS treated @ 600mm centres Insulation All partitions 25mm Acoustic insulation.

LOAD-BEARING INTERNAL PARTITIONS

Runners 38x89mm CLS treated

Studs 38x89mm CLS treated @ 400mm centres

Mid Dwangs 38x89mm CLS treated

Sheathing 9mm OSB nailed to one side only Insulation All partitions 25mm Acoustic insulation.

FIRST FLOOR Joists 45x195mm treated regularized whitewood

@ 400mm centres, <u>or</u> engineered roof trusses at centres approved by Structural

Engineer

Flooring 22mm thick Moisture Resistant T&G

Chipboard flooring, glued and annular ring

nailed.

ROOF Trusses Generally 25/30 degree Fink Trusses or

40/45 degree Stub or Attic, TRADA

designed

Wind Bracing 22x100mm whitewood, sawn treated. Sarking 9mm OSB exterior grade sheathing.

Felt 22kg reinforced grade 1F or VP400 roofing

membrane.

Counter Battens 12x38mm whitewood sawn treated.
Tile Battens 38x50mm whitewood sawn treated.

Roof Tiles Redland "Grovebury" precast concrete roof

tiles c/w fixngs - colours Slate Grey, Tudor Brown or Terra Cotta [subject to Planning

Consent]

Barge Board 22x170mm redwood dressed treated. Fascia Board 22x230mm redwood dressed treated.

Soffit Board 9.5m Far Eastern Plywood, painted as

required.

Ventilation Over fascia pattern.



WINDOWS

Scandinavian severe exposure rated laminated redwood windows. All double glazed with low emissive energy saving glass and Argon gas filled cavities, u-value 1.1 -

1.4 W/m2K.

Alternatively, we can offer PVC windows or locally manufacture hardwood windows. Price variation can be

provided on application.

ROOF WINDOWS

Velux [o.e.a.] severe exposure rated laminated redwood roof windows. All double glazed with low emissive energy saving glass and Argon gas filled cavities, u-value 1.4 -1.5 W/m2K.

EXTERIOR DOORS

Front and/or Rear Locally manufactured hardwood door-sets

> with 3-point locking system, [4] stainless steel hinges and SAA furniture. All double glazed with low emissive energy saving

glass.

Patio Doors NorDan laminated redwood pre-glazed

> sliding patio doors, where applicable. All double glazed with low emissive energy saving glass and Argon gas filled cavities.

u-value 1. - 1.4 W/m2K.

"Dooria" SKOG Oak veneered [or equal], pre-finished, INTERIOR DOORS

hollow core door-sets complete with pre-finished door

frames.

DOOR FURNITURE "Karcher" [o.e.a.] stainless steel "designer range"

furniture.

INSULATION Loft/Roof Space 350mm Knauf Earthwool 44 insulation in [2]

Layers [200mm + 150mm]

140mm Knauf Frametherm 35 insulation **External Walls**

> between studs with 25mm thick Kingspan [o.e.a.] rigid insulation over inside face of studs. 25x50mm whitewood sawn treated brandering fitted over to create a service

Under Floor 200mm Knauf Earthwool 44 insulation on

9.5mm OSB between joists, supported on



100mm wide x 9mm OSB strips, pinned to

underside of joists.

Internal Partitions 25mm acoustic insulation to all internal

partitions

Coombs 100mm Kingspan [o.e.a.], between trusses,

to rafter element of upper floor roof, with 25mm Kingspan [o.e.a.] lining etc., as per

external walls.

90mm Knauf Frametherm 35, between truses, to vertical comb section, with 25mm Kingspan [o.e.a.] lining etc., as per external

walls.

Insulation specification may vary to satisfy specific SAP rating calculations

PLASTERBOARD External Walls 12.5mm T/E Foil Backed [including garage]

> 12.5mm T/E Plain [single storey] Ceilings Ceilings Internal Partitions Garage Ceiling Toilets/Bathrooms

Coving

12.5mm T/E Fireline [multi storey] 12.5mm T/E 10kg/m2 for soundbloc 12.5mm T/E Fireline [integral garage] 12.5mm T/E Moisture Resistant. [Walls] Gyproc Coving to Lounge/Kitchen/

Dining Room.

Ceilings Accessories – Resilient bars are fitted at appropriate centres to underside of flooring ties, of attic trusses, to minimize sound transfer between separating floors, in accordance with latest Building Regulations update.

STAIR Pre-fabricated staircase, softwood stringers and treads,

MDF risers, Burbidge [o.e.a.] handrails and spindles, as

required.

FINISHINGS Redwood facings, skirtings, cills, aprons and window

ingoes.

SUNDRIES

Wardobes Chrome wardrobe hanging rails and fixings.

[1] full width MDF shelf

Loft Access [1] No. Fakro pre-fabricated, insulated loft access hatch

c/w folding redwood ladder, or [1] No. Fakro pre-

fabricated, insulated comb access door, as appropriate.



Cyl. Cupbd. [1] No. slatted shelf to provide dry linen storage

KITCHEN/UTILITY Choose, and design, your own kitchen using local or

national Suppliers. A Prime Cost Sum is included in the kit price, which should be sufficient to fit out the house selected, however, you can increase, or decrease, your

budget as required.

SANITARY WARE All as Kitchen/Utility.

CENTRAL HEATING Allowance has been made for the supply and installation

of an Air Source Heat Pump, as standard, feeding a wet system of under-floor heating [G.F. only] and radiators [F.F.]. We are also able to supply and install specialist Heat Recovery Systems, Solar heat sources etc., as

required.

ELECTRICAL A standard number of sockets and light fittings, TV and

telephone points are allowed for in accordance with current building standards. However, you can arrange the electrical layout, to suit your own requirements. Additional

fittings requested will incur additional costs.

DECORATION Internal walls and ceilings will receive two coats of trade

emulsion paint [Magnolia to walls and White to ceilings]. All redwood finishings to receive three coats of clear varnish. External face of windows, fascias, barge boards and soffits to receive one coat primer and two coats Jotun Optimal. Colour to be confirmed. Recommend windows factory finished, one colour both sides. External painting

of timber cladding boards is <u>not included</u> unless otherwise requested. [see separate paint spec.]

LANDSCAPING The house site excavations are landscaped on

completion of building works, using suitable excavated material, previously retained on site, only. Topsoil can be imported onto site, if required by Client, at an additional cost. Sufficient stone chip path, for access, has been

allowed.

GENERAL DESIGN All elements of our standard house kit construction meet

with the requirements of the local authorities and the National House Building Council. We can provide independent "Professional Supervision", together with a



Six Year Warranty, on completion, **if required,** at an additional cost.